

Park Square – Campbelltown



Coltart Earley Architects - Argyll Community Housing Association

Project Information

Type of Building: 3-storey newbuild apartment blocks x 2
Glazing System: Windoor System 1000 Light
Quantity: 24 enclosed balconies
Construction: The stacks of balconies span from ground floor to 2nd floor with a stack in each corner and a double width stack centrally. Elements span from floor to floor and comprise a glazed balustrade section of clear laminated float safety glass and an upper section featuring a sliding folding opening section in clear toughened glass. A double handrail is fitted externally which comprises an aluminium tube and a tensioned stainless steel wire rope.

Completion Date: 2013

cpd provider

